



Buncombe County Board of Commissioners

Request for Board Action

Meeting Date: 6/18/2019

Consent Agenda

Department: Solid Waste

Presenter(s):

Contact(s): Dane: 828-545-8258

Subject: North Landfill Slope Valve/Well Cluster Extensions

Brief Summary: Following a Request for Qualifications (RFQ) Process, SCS was approved by the Board of Commissioners to provide prime engineering services for the Buncombe County Solid Waste Department. SCS and Buncombe County executed a formal agreement on August 23rd, 2018 and all subsequent and proposed engineering work has been approved via Task Orders.

Under this Task Order Number 19-24, SCS Engineers to extend five valve/well combination clusters on the North landfill slope, to accommodate side slope filling sequence.

Recommended Motion & Requested Action: Approval for County Manager to sign and execute SCS Task Order Number 19-24 in the amount of \$33,027.00

County Manager's comments and Recommendation: The County Manager agrees with this recommendation.

EXHIBIT C
Task Order Number 19-24
North Slope Valve/Well Cluster Extensions
Buncombe County Solid Waste Department

SCOPE OF SERVICES

Scope of Work Description

SCS is pleased to provide this proposal to visit the Buncombe County Solid Waste Management Facility to complete the following tasks:

1. Extend five valve/well combination clusters on upper half of the North Slope.
2. Provide materials to extend the five valve/well clusters as well as materials needed for the next well raising event along the North Slope.

SCS will provide two technicians for up to two days, including travel, to complete this work.

Additionally, the following materials will be purchased:

1. 5 ea. – 6-inch Type 57 gear box
2. 5 ea. – 6-inch Type 57 hand wheel
3. 5 ea. – 4-inch valve handles
4. 10 ea. – 10-foot valve stem extensions for 6-inch gear valves (gas)
5. 5 ea. – 10-foot valve stem extensions for 4-inch ball valve (leachate)
6. 5 ea. – 6-foot custom stem replacement for 6-inch gas valve
7. 5 ea. – 10-foot custom intermediate stem for 4-inch leachate valve
8. 400 ft. – 6-inch SDR-17 HDPE pipe
9. 200 ft. – 4-inch SDR-17 HDPE pipe
10. 200 ft. – 2-inch SDR-11 HDPE pipe

Deliverables and Schedule


Work will commence within 14 days of notice to proceed and will require no more than 2 days to complete.

Compensation

Compensation to the Contractor for services performed under this Task Order will be in accordance with the (lump sum) or time and materials (*circle one*) invoice method and shall be based upon the fees as set out in the Agreement.

SCS ENGINEERS, PC proposes to complete this Task for a fee of **\$33,027**. This fee, which is based on the assumptions provided in this Task Order proposal, shall not be exceeded without written authorization from the County.

The above lump sum price is based on an event fee of \$6,000, plus \$27,027 for purchase of materials.

<p>BUNCOMBE COUNTY BOARD OF COUNTY COMMISSIONERS</p> <p>By:</p> <hr/> <p>(Signature)</p> <hr/> <p>(Printed Name)</p> <hr/> <p>(Title)</p> <hr/> <p>(Date)</p>	<p>CONTRACTOR SCS ENGINEERS, PC</p> <p>By:</p>  <hr/> <p>(Signature)</p> <p>Tony Cartee</p> <hr/> <p>(Printed Name)</p> <p>Regional Manager</p> <hr/> <p>(Title)</p> <p>5/28/19</p> <hr/> <p>(Date)</p>
---	--

THIS INSTRUMENT HAS BEEN PRE-AUDITED IN THE MANNER REQUIRED BY THE
LOCAL GOVERNMENT AND FISCAL CONTROL ACT

Finance Director

Approved as to form

County Attorney/County Staff Attorney