

1 H201 **HVAC PLAN**
1/8" = 1'-0"

KEY NOTES

1. INSTALL UNIT 30" ABOVE CEILING TO PROVIDE REQUIRED CLEARANCE UNDERNEATH THE UNIT.
2. PROVIDE 18" PLENUM.
3. EXHAUST LOUVER.
4. INTAKE LOUVER.
5. INSTALL UNIT MAX 2" ABOVE CEILING.
6. SERVICE CLEARANCE.
7. TRANSFER AIR DUCT.
8. DRYER EXHAUST DUCT. PROVIDE WALL CAP WITH BACK DRAFT DAMPER. LOCATE WALL CAP MIN 3'-0" FROM BUILDING OPENINGS.
9. DRYER EXHAUST DUCT DN. TERMINATE 6'-0" ABOVE THE FLOOR. PROVIDE WALL SUPPORT.
10. INSTALL BOTTOM OR HOSE REEL AT THE SAME ELEVATION OF THE GARAGE DOOR RAIL. (TYP OF 4)
11. PROVIDE BACK DRAFT DAMPER. INSTALL 3'-0" ABOVE THE GARAGE DOOR. (TYP OF 4)
12. THERMOSTAT SHALL BE INSTALLED ON UTILITY POLE. COORDINATE INSTALLATION OF UNDERGROUND CONDUIT WITH GC AND OTHER TRADES.
13. KITCHEN HOOD EXHAUST DUCT DN TO RESIDENTIAL STYLE KITCHEN HOOD.
14. KITCHEN HOOD EXHAUST DUCT UP TO GRAVITY RELIEF ON ROOF. PROVIDE 10" DIAMETER ALUMINUM GRAVITY RELIEF WITH INSECT SCREEN ON 12" ROOF CURB. GRAVITY RELIEF SHALL BE MODEL GRSR-10 AS MANUFACTURED BY GREENHECK OR APORVED EQUAL BY LOREN COOK COMPANY OR TWIN CITY FAN.
15. SUPPLY GRILLE IN KEY ROOM 128

CPL | Architecture Engineering Planning
400 Bellemeade Street Suite 401,
Greensboro, NC 27401
CPLteam.com

NC ENGINEERING FIRM LICENSE NO. C-2194

PROJECT INFORMATION

Project Number
15716.00

Client Name
BUNCOMBE COUNTY

Project Name
FLEET SERVICES COMPLEX

RIVERSIDE DRIVE

Project Address
ASHEVILLE, NC 28804

PROJECT ISSUE & REVISION SCHEDULE

vv	Date	Description
1	4/24/2023	Addendum 3

PROFESSIONAL STAMPS

SHEET INFORMATION

Issued
03/20/2023

Scale
1/8" = 1'-0"

Project Status
-

Drawn By
-

Checked By
--

Drawing Title
FIRST FLOOR DUCTWORK PLAN

Drawing Number
H201

4/24/2023 3:35:32 PM <project location>\3 Design & Project Files on BIM 360