

TRANSPORTATION IMPACT ANALYSIS

Pond Road Development

Buncombe County, NC

Prepared for Fall Line Development



Transportation Impact Analysis

Pond Road Development Buncombe County, NC

Prepared for Fall Line Development February 7, 2020

Analysis by: Andrew Hayes, P.E., PTOE

Drafting/Graphics by: Tou Lee

Reviewed by: Robert Gey, P.E.

Sealed by: Andrew Hayes, P.E., PTOE





This report is printed on recycled paper with 30% post-consumer content. All paper is FSC Certified. The entire document, including binding, is 100% recyclable.



This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of, or improper reliance on, this document by others without written authorization and adaptation by DAVENPORT shall be without liability to DAVENPORT and shall be a violation of the agreement between DAVENPORT and the client.

Pond Road Development - Transportation Impact Analysis Buncombe County, NC February 7, 2020

Table of Contents

1.0 Introduction	3
1.1 Site Description	3
1.2 Project Description	3
1.3 Site Accesses	3
1.4 Study Area	3
Figure 1 - Site Plan	5
Figure 2 - Vicinity Map	6
2.0 Existing Conditions	7
2.1 Inventory	7
2.2 Existing Traffic Volumes	8
Figure 3 – Existing Lane Geometry	9
Figure 4 - Existing Traffic Volumes	10
3.0 2020 Future No Build Conditions	11
3.1 Approved Developments	11
3.2 Committed Improvements	
3.3 Future No Build Traffic Volumes	
Figure 5 – 2022 Future No Build Volumes	12
4.0 Methodology	
4.1 Base Assumptions and Standards	
5.0 2022 Build Phase 1 Conditions	
5.1 Trip Generation	
5.2 Trip Distribution	
5.3 2022 Build Volumes	
Figure 6 – Phase 1 Trip Distribution	
Figure 7 – Phase 1 Site Trips	
Figure 8 – Phase 1 Build Volumes	
6.0 2022 Capacity Analysis	
6.1 Level of Service Evaluation Criteria	
6.2 Build Level of Service Discussion	
6.3 Level of Service Results	
Figure 9 – Phase 1 Recommended Improvements	
7.0 2022 Queue Analysis	
8.0 Phase 1 Turn Lane Warrants	
9.0 2023 Build Phase 2 Conditions	
9.1 Trip Generation	
9.2 Trip Distribution	
9.3 2023 Build Volumes	
Figure 10 – 2023 Future No Build Volumes	
Figure 11 – Phase 2 Trip Distribution	
Figure 12 – Phase 2 Site Trips	32

Figure 13 – Phase 2 Build Volumes	
10.0 2023 Capacity Analysis	34
10.1 Build Level of Service Discussion	
10.2 Level of Service Results	36
Figure 14 – Phase 2 Recommended Improvements	40
11.0 ² 023 Queue Analysis	
12.0 Phase 2 Turn Lane Warrants	
13.0 I-2513 Capacity Analysis	
14.0 Summary and Conclusion	
1110 0 MIIIII MI MI MI COILCIMOIOII	•••••••••••••••••••••••••••••••••••••••

Pond Road Development - Transportation Impact Analysis Buncombe County, NC February 7, 2020

1.0 Introduction

1.1 Site Description

The proposed Pond Road development is located on the northwest of Pond Road at House Lane in Buncombe County, North Carolina. DAVENPORT was retained to analyze the potential traffic impacts of this development and to identify transportation improvements that may be required to accommodate the impacts of both background traffic and new development traffic. The findings from the analysis are summarized in this report. The site plan is shown in Figure 1.

1.2 Project Description

This development is planned to consist of two phases. Phase 1 consists of 280 mid-rise multifamily dwelling units on the south side of the property. Phase 1 is expected to open in 2022. Phase 2 consists of 32 single family dwelling units, 80 low-rise multifamily dwelling units, and 295 mid-rise multifamily dwelling units. Low-rise multifamily includes apartments, townhouses, and condominiums located within the same building with at least three other dwelling units and that have one to two levels. Mid-rise multifamily include apartments,townhouses, and condominiums that have between three and 10 levels. Phase 2 is expected to be open in 2023. The scope of this study was confirmed with NCDOT staff. The approved NCDOT TIA Scoping Checklist for the project is included in the Appendix.

1.3 Site Accesses

The development will utilize two accesses. The southern site access (Site Access 1) will be a right-in/out on Pond Road. The northern site access (Site Access 2) will be a full movement site access on Pond Road. The access locations are shown in the site plan in Figure 1.

1.4 Study Area

A vicinity map of all study intersections is provided in Figure 2. The following intersections were included in the study:

- 1. NC 112 (Sardis Road) at SR 3431 (Pond Road) (Unsignalized)
- 2. SR 3431 (Pond Road) at SR 3426 (McIntosh Road) (Signalized)
- 3. NC 191 (Brevard Road) at SR 3431 (Pond Road) (Signalized)
- 4. NC 191 (Brevard Road) at SR 3600 (Farmers Market) / SR 3414 (East Oakview Road) (Signalized)
- 5. NC 191 (Brevard Road) at I-40 Eastbound Ramp (Signalized)
- 6. NC 191 (Brevard Road) at I-40 Westbound Ramp (Signalized)
- 7. NC 191 (Brevard Road) at NC 112 (Sardis Road) / Ridgefield Boulevard (Signalized)
- 8. NC 112 (Sand Hill Road / Sardis Road) at SR 3412 (Sand Hill Road) (Signalized)

SR 3431 (Pond Road) at Site Access 1 (proposed unsignalized)
 SR 3431 (Pond Road) at Site Access 2 (proposed unsignalized)

The above-mentioned intersections were analyzed for the following scenarios:

- 2020 Existing Conditions
- 2022 Future No Build Conditions
- 2022 Build Phase 1 Conditions
- 2022 Build Phase 1 with Improvements
- 2023 Future No Build Conditions
- 2023 Build Phase 1 Conditions
- 2023 Build Phase 1 with Improvements





FIGURE 1 SITE PLAN






FIGURE 2 VICINITY MAP STUDY INTERSECTIONS BACKGROUND PROPOSED

2.0 Existing Conditions

2.1 Inventory


A field investigation was conducted by DAVENPORT staff to determine the existing roadway conditions in the study area. Table 2.1 presents a summary of this investigation. Figure 3 presents the existing lane geometry.


Table 2.1 - Street Inventory								
Facility Name	Route #	Typical Cross Section	Pavement Width	Speed Limit	Maintained By			
Pond Road	SR 3431	2 lanes undivided	Approx. 20'	35 MPH	NCDOT			
Sardis Road	NC 112	2 lanes undivided	Approx. 22'	45 MPH	NCDOT			
McIntosh Road	SR 3426	2 lanes undivided	Approx. 20'	35 MPH	NCDOT			
Brevard Road	NC 191	4 lanes divided	Approx. 72'	45 MPH	NCDOT			
Farmers Market	SR 3600	2 lanes undivided	Approx. 50'	20 MPH Design Speed	NCDOT			
East Oakview Road	SR 3414	2 lanes undivided	Approx. 24'	25 MPH	NCDOT			
I-40	-	4 lanes divided	Approx. 120'	60 MPH	NCDOT			
Sand Hill Road	NC 112 SR 3412	2 lanes undivided	Approx. 22'	45 MPH	NCDOT			

2.2 Existing Traffic Volumes

Existing traffic volumes for this project were provided by Quality Counts. Table 2.2 contains the dates these counts were conducted. Figure 4 shows existing AM and PM peak hour volumes. More information can be found in the Traffic Volume Data section of the appendix.

Table 2.2 - Traffic Volume Data							
Count Location:	Date Taken:	Collection by:					
Sardis Road at Pond Road	1/30/2020	Quality Counts					
McIntosh Road at Pond Road	1/30/2020	Quality Counts					
Brevard Road at Pond Road	1/30/2020	Quality Counts					
Brevard Road at Farmers Market	1/9/2020	Quality Counts					
Brevard Road at I-40 Eastbound Ramps	1/9/2020	Quality Counts					
Brevard Road at I-40 Westbound Ramps	1/9/2020	Quality Counts					
Brevard Road at Sardis Road/Ridgefield Boulevard	1/9/2020	Quality Counts					
Sand Hill Road at Sardis Road	1/9/2020	Quality Counts					





3.0 2020 Future No Build Conditions

3.1 Approved Developments


Approved developments are developments that have been recently approved in the area, but not yet constructed. Pond Road Subdivision is an approved development on Pond Road and south of McIntosh Road. The development is expected to consist of 100 single family dwelling units, 140 low-rise multifamily dwelling units, and 240 mid-rise multifamily dwelling units. The development is expected to be built in two phases; however, for this analysis, it will be assumed that both phases are built before Phase 1 of this project. The committed improvement for this development is 150' southbound right turn lane on Pond Road at the intersection with Sardis Road.

3.2 Committed Improvements

Committed Improvements are improvements that are planned by NCDOT, a local municipality, or a developer in the area, but not yet constructed. U-6047 is a NCDOT STIP project, which will improve the intersection of Sardis Road at Pond Road. Construction is planned for 2025. I-2513 is a NCDOT STIP project, which will upgrade I-26, I-240, I-40, and ramps. I-2513 project impact figure can be found in the appendix.

3.3 Future No Build Traffic Volumes

Based on the scoping with NCDOT, future no build volumes were computed by applying a 1.5% growth rate.



4.0 Methodology

4.1 Base Assumptions and Standards

In general, the analysis for this project was conducted utilizing NCDOT Congestion Management standards and local guidelines. The following table contains a summary of the base assumptions:

Table 4.1 - Assumptions						
Background Traffic Growth	1.5%					
Signal Timing/Phasing	Based on signal plans obtained from NCDOT					
Analysis Software	Synchro/SimTraffic Version 10.0 (signalized and unsignalized)					
Lane widths	12-feet					
Peak Hour Factor	0.90 for all movements expect In the AM, 0.75 was used traffic turning into and off of McIntosh Road at the intersection with Pond Road, since IC Imagine school is on McIntosh Road					
Heavy Vehicle Percentage	2%					

5.0 2022 Build Phase 1 Conditions

5.1 Trip Generation

Phase 1 is planned to consist of 280 dwelling units of multifamily housing. Local data based on the development was used, as agreed upon with NCDOT. Table 5.1 presents the results.

	Table 5.1 - ITE Trip Generation									
	Average Weekday Driveway Volumes 24						AM F Ho		PM F Ho	
Phase	<u>Land Use</u>	ITE Land Use Code	<u>Size</u>		<u>Data</u> <u>Source</u>	<u>Volume</u>	Enter	<u>Exit</u>	Enter	<u>Exit</u>
1	Multifamily (Mid-Rise)	221	280 Dwelling Units		Equation - Adjacent	1,524	24	70	73	46
	Phase 1 Trips				1,524	24	70	73	46	

5.2 Trip Distribution


Site trips for this proposed development were distributed based existing travel patterns and engineering judgement. The trip distribution model (shown in Figure 6) was confirmed with the NCDOT, and utilizes the following overall directional percentages:


- 20% to/from the west on Brevard Road
- 25% to/from the east on I-40
- 5% to/from the west on I-40
- 5% to/from McIntosh Road
- 20% to/from the west on Sand Hill Road
- 9% to/from the north on Sand Hill Road
- 8% to/from the north on Brevard Road
- 6% to/from the south on Brevard Road
- 2% to/from Ridgefield Boulevard


5.3 2022 Build Volumes

The 2020 build volumes were obtained by summing future no build volumes and site trips. Site trips are shown in Figure 7.

The future build volume totals for AM and PM peaks are shown in Figure 8.







6.0 2022 Capacity Analysis

6.1 Level of Service Evaluation Criteria

The Transportation Research Board's Highway Capacity Manual (HCM) utilizes a term "level of service" to measure how traffic operates in intersections and on roadway segments. There are currently six levels of service ranging from A to F. Level of service "A" represents low-volume traffic operations and Level of Service "F" represents high-volume, oversaturated traffic operations. However, in very congested areas, a simple LOS evaluation technique may not be sufficient to determine the true impact of a project. Synchro Traffic Modeling software was used to determine the level of service for studied intersections. Note for unsignalized intersection analysis, the level of service noted is for the worst approach of the intersection. This is typically the left turn movement for the side street approach, due to the number of opposing movements. All worksheet reports from the analyses can be found in the Appendix.

In accordance with NCDOT guidelines, mitigation is required when the Build condition exceeds the No-Build conditions by any of the following minimum thresholds:

- 1. The average delay at an intersection or individual approach increases by 25% or greater, or
- 2. The Level of Service degrades by at least one level above LOS D, or
- 3. Level of Service is "F"

Table 6.1 – Highway Capacity Manual							
	Levels of Service and C	ontrol Delay Criteria					
Signalized Intersection Unsignalized Intersection							
Level of Service	Control Delay Per vehicle (sec)	Level of Service	Delay Range (sec)				
Α	≤ 10	Α	≤ 10				
В	> 10 and ≤ 20	В	> 10 and ≤ 15				
С	> 20 and ≤ 35	С	> 15 and ≤ 25				
D	> 35 and ≤ 55	D	> 25 and ≤ 35				
E	> 55 and ≤ 80	E	> 35 and ≤ 50				
F	> 80	F	> 50				

6.2 Build Level of Service Discussion

The results of the level of service analysis are discussed by intersection below. The LOS results tables can be found in Section 6.3.

Sardis Road at Pond Road

For all scenarios with Sardis Road at Pond Road operating as a stop controlled intersection, the intersection operates as an LOS F for both the AM and PM. Signalizing this intersection would greatly reduce delay for the southbound direction with minimal delay impacts for the east- and westbound direction. Signalizing this intersection is recommended.

Pond Road at Site Access 1

This intersection operates as a right-in and out, which will mostly serve Phase 1. The intersection operates at LOS A for the eastbound direction in both AM and PM Peak Hours. No improvements are recommended.

Pond Road at Site Access 2

This intersection is proposed to have full access. The intersection operates at LOS B for eastbound direction and LOS A in the northbound direction in both Peak Hours. <u>No improvements are recommended.</u>

Pond Road at McIntosh Road

The intersection of Pond Road at McIntosh Road is near a school. Being near a school the intersection is expected to operate with high delay during the AM peak hour. For all scenarios, the intersection operates at LOS E in the AM Peak Hour and LOS B in the PM Peak Hour. No improvements are recommended.

Pond Road at Brevard Road

In all scenarios, this intersection operations at LOS C or better. <u>No improvements are</u> recommended.

Brevard Road at Farmers Market

In all scenarios, this intersection operations at LOS B or better. <u>No improvements are recommended.</u>

Brevard Road at I-40 EB Ramp

In all scenarios, this intersection operations at LOS B or better. <u>No improvements are</u> recommended.

Brevard Road at I-40 WB Ramp / South Bear Creek Road

The intersection of Brevard Road at I-40 WB Ramp and South Bear Creek Road operates at a LOS D in the AM Peak Hour for all scenarios. The interaction operates at a LOS C or better in the PM Peak Hour for all scenarios. No improvements are recommended.

Brevard Road at Sardis Road / Ridgefield Boulevard

The intersection of Brevard Road at Sardis Road and Ridgefield Boulevard operates at a LOS D in the AM Peak Hour for all scenarios. The intersection is expected to degrade from LOS D in existing scenario to LOS E of both No Build and Build in the PM Peak Hour. No improvements are recommended.

Sand Hill Road at Sardis Road

The intersection of Brevard Road at Sardis Road and Ridgefield Boulevard operates at a LOS D in the AM Peak Hour and LOS E in the PM Peak Hour for all scenarios. <u>No improvements are recommended.</u>

6.3 Level of Service Results

The Level of Service for the 2019 Existing through Build conditions are shown in Tables 6.2 – 6.11.

Table 6.2 - Sardis Road at Pond Road						
Scenario	Overall	Level of	Level of Service by Approach (Delay in sec/veh)			
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound	
		AM Peak Hour	r			
Existing	-	A (8.9)	A (0.0)	-	F (88.2)	
2022 No Build	-	A (9.1)	A (0.0)	-	F (70.7)	
2022 Build Phase 1	-	A (9.1)	A (0.0)	-	F (106.7)	
2022 Build Phase 1 - Signal	B (13.9)	A (12.8)	A (9.2)	-	C (30.0)	
		PM Peak Hour				
Existing	-	B (10.9)	A (0.0)	-	F (>300)	
2022 No Build	-	B (11.4)	A (0.0)	-	F (>300)	
2022 Build Phase 1	-	B (11.8)	A (0.0)	-	F (>300)	
2022 Build Phase 1 - Signal	B (13.3)	A (8.4)	B (13.6)	-	C (33.8)	

Table 6.3 - Pond Road at Site Access 1						
Scenario	Overall	Level of	Level of Service by Approach (Delay in sec/veh)			
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound	
		AM Peak Hour	•			
2022 Build Phase 1	-	A (9.5)	-	A (0.0)	A (0.0)	
PM Peak Hour						
2022 Build Phase 1	-	A (9.2)	-	A (0.0)	A (0.0)	

Table 6.4 - Pond Road at Site Access 2							
Scenario	Overall	Level of	Level of Service by Approach (Delay in sec/veh)				
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
	AM Peak Hour						
2022 Build Phase 1	-	B (11.4)	-	A (7.7)	A (0.0)		
PM Peak Hour							
2022 Build Phase 1	-	B (11.4)	-	A (7.7)	A (0.0)		

Table 6.5 - Pond Road at McIntosh Road								
Scenario	Overall	Level of	Level of Service by Approach (Delay in sec/veh)					
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound			
	AM Peak Hour							
Existing	E (55.5)	F (106.6)	-	A (7.9)	B (17.2)			
2022 No Build	E (63.4)	F (132.0)	-	A (9.0)	B (18.7)			
2022 Build Phase 1	E (62.6)	F (133.4)	-	A (9.8)	B (19.4)			
	PM Peak Hour							
Existing	B (10.7)	B (13.0)	-	A (7.7)	B (10.5)			
2022 No Build	B (11.7)	B (15.2)	-	A (8.0)	B (11.6)			
2022 Build Phase 1	B (12.1)	B (16.2)	-	A (8.1)	B (12.1)			

Table 6.6 - Pond Road at Brevard Road						
Casmaria	Overall	Level of	Level of Service by Approach (Delay in sec/veh)			
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound	
		AM Peak Hou				
Existing	C (22.5)	B (14.8)	C (23.9)	D (35.1)	-	
2022 No Build	C (27.1)	B (15.4)	C (30.1)	D (43.2)	-	
2022 Build Phase 1	C (30.7)	B (15.5)	C (31.9)	D (54.0)	-	
		PM Peak Hour				
Existing	B (16.1)	B (15.2)	B (11.9)	C (28.9)	-	
2022 No Build	B (17.4)	B (15.3)	B (14.1)	C (29.2)	-	
2022 Build Phase 1	B (18.0)	B (15.6)	B (14.7)	C (30.1)	-	

Table 6.7 - Brevard Road at Farmers Market					
Scenario	Overall	Level of	Service by App	roach (Delay ir	sec/veh)
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound
	AM Peak Hour				
Existing	B (13.3)	B (10.3)	B 15.2)	C (31.5)	C (29.3)
2022 No Build	B (13.8)	B (10.5)	B (16.1)	C (31.5)	C (29.3)
2022 Build Phase 1	B (14.0)	B (10.4)	B (16.5)	C (31.5)	C (29.3)
		PM Peak Hour			
Existing	B (13.4)	B (10.6)	B (11.7)	C (33.4)	C (33.3)
2022 No Build	B (14.1)	B (12.5)	B (11.7)	C (33.6)	C (33.5)
2022 Build Phase 1	B (14.1)	B (12.7)	B (11.7)	C (33.6)	C (33.5)


Table 6.8 - Brevard Road at I-40 EB Ramp					
Scenario	Overall	Level of	Service by App	roach (Delay ir	sec/veh)
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound
		AM Peak Hour	•		
Existing	B (10.2)	B (10.7)	A (6.3)	-	C (26.7)
2022 No Build	B (10.5)	B (11.0)	A (7.0)	-	C (25.5)
2022 Build Phase 1	B (10.6)	B (11.3)	A (7.2)	-	C (24.9)
		PM Peak Hour			
Existing	A (9.8)	A (9.1)	B (10.2)	-	B (13.9)
2022 No Build	B (10.4)	A (9.1)	B (10.9)	-	B (18.0)
2022 Build Phase 1	B (10.5)	A (9.0)	B (11.1)	-	B (18.2)

Table 6.9 - NC 55 Bypass at I-40 WB Ramp / South Bear Creek Road					
Scenario	Overall	Level of Service by Approach (Delay in sec/veh)			
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound
AM Peak Hour					
Existing	D (38.3)	B (17.5)	A (4.9)	D (35.4)	F (94.8)
2022 No Build	D (47.2)	B (17.8)	A (5.2)	D (53.2)	F (117.1)
2022 Build Phase 1	D (49.4)	B (17.9)	A (5.8)	E (59.0)	F (122.2)
		PM Peak Hour	•		
Existing	B (19.8)	C (20.1)	B (18.7)	A (5.2)	C (23.5)
2022 No Build	C (21.1)	C (21.2)	C (20.1)	A (5.2)	C (25.2)
2022 Build Phase 1	C (22.4)	C (21.8)	C (20.8)	A (5.2)	C (27.7)

Table 6.10 - Brevard Road at Sardis Road / Ridgefield Boulevard					
Scenario	Overall	Level of	Service by App	roach (Delay ir	sec/veh)
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound
		AM Peak Hou	r		
Existing	D (45.5)	E (58.9)	E (59.6)	D (38.9)	D (38.1)
2022 No Build	D (45.9)	E (59.1)	E (59.4)	D (39.0)	D (38.8)
2022 Build Phase 1	D (46.0)	E (59.0)	E (59.5)	D (39.2)	D (38.9)
		PM Peak Hour	•		
Existing	D (54.4)	E (57.1)	E (75.1)	D (48.6)	D (43.4)
2022 No Build	E (55.7)	E (57.0)	E (76.2)	D (51.0)	D (44.7)
2022 Build Phase 1	E (56.2)	E (57.4)	E (76.3)	D (52.1)	D (44.6)

Table 6.11 - Sand Hill Road at Sardis Road						
	Overall	Level of	Service by App	roach (Delay ir	n sec/veh)	
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound	
	AM Peak Hour					
Existing	D (40.9)	C (32.2)	C (22.1)	-	E (72.4)	
2022 No Build	D (46.4)	D (36.8)	C (22.6)	-	F (85.0)	
2022 Build Phase 1	D (47.3)	D (37.2)	C (22.8)	-	F (87.8)	
		PM Peak Hour				
Existing	E (60.7)	C (23.6)	D (38.6)	-	F (155.6)	
2022 No Build	E (67.3)	C (24.4)	D (44.8)	-	F (172.3)	
2022 Build Phase 1	E (68.2)	C (24.0)	D (48.2)	-	F (170.4)	

Figure 11 illustrates the recommended improvements for the Phase 1 Build-out conditions.



7.0 2022 Queue Analysis

Queuing analysis was conducted using SimTraffic simulation for the study intersections, based on a standard 15-minute seeding time and a 60-minute recording time. The maximum queue lengths are shown below, along with existing turn lane lengths. All queue reports can be found in the appendix. The queue length lengths are the highest value of AM or PM analysis.

In accordance with NCDOT guidelines, mitigation is required when the Build condition exceeds the No-Build conditions by any of the following minimum thresholds:

- 1. Increase of 50' or more in queue length
- 2. Left-turn and/or right-turn lane warrants (NCDOT's Policy on Street and Driveway Access to North Carolina Highway) are identified
- 3. Build with Capacity Improvements queue exceeds existing storage length

Table 7.1 -Sardis Road at Pond Road					
	Queue Length (ft)				
2022 Scenario	Recommended Storage	No Build	Build	Signal	
Eastbound Left	150	95	98	135	
Eastbound Through	Full	-	-	244	
Westbound	Full	24	22	285	
Southbound Left	Full	184	258	134	
Southbound Right	150	110	250	161	

Table 7.2 - Pond Road at Site Access 1				
	Queue Length (ft)			
2022 Scenario	Recommended Storage	No Build	Build	
Eastbound	Full	-	48	

Table 7.3 - Pond Road at Site Access 2					
	Queue Length (ft)				
2022 Scenario	Recommended Storage	No Build	Build		
Eastbound	Full	-	53		
Northbound	Full	-	55		

Table 7.4 - Pond Road at McIntosh Road					
	Queue Length (ft)				
2022 Scenario	Recommended Storage	No Build	Build		
Eastbound	Full	722	726		
Northbound	Full	251	363		
Southbound	Full	282	274		

Table 7.5 - Brevard Road at Pond Road						
	Queue	Queue Length (ft)				
2022 Scenario	Recommended Storage	No Build	Build			
Eastbound U-Turn	350	54	50			
Eastbound Through	Full	159	150			
Eastbound Right	350	229	226			
Westbound Left	350	220	219			
Westbound Through	Full	134	148			
Northbound Left	Full	1065	1065			
Northbound Right	100	200	200			

Table 7.6 - Brevard Road at Farmers Market					
	Queue Length (ft)				
2022 Scenario	Recommended Storage	No Build	Build		
Eastbound Left	Full	102	96		
Eastbound Through	Full	179	162		
Eastbound Right	Full	69	69		
Westbound Left	325	77	84		
Westbound Through	Full	241	239		
Westbound Right	325	33	38		
Northbound Left	230	96	108		
Northbound Through	Full	96	87		
Southbound Left	Full	77	53		
Southbound Through	150	120	138		

Table 7.7 - Brevard Road at I-40 EB Ramp					
	Queue	e Length (ft)			
2022 Scenario	Recommended Storage	No Build	Build		
Eastbound Left	650	174	187		
Eastbound Through	Full	424	460		
Westbound Through	Full	186	180		
Westbound Right	Full	168	148		
Southbound Left	Full	101	128		
Southbound Right	25	96	112		

Table 7.8 - Brevard Road at I-40 WB Ramp / South Bear Creek Road					
	Queue Length (ft)				
2022 Scenario	Recommended Storage	No Build	Build		
Eastbound Left	250	28	28		
Eastbound Through	Full	286	287		
Westbound Left	100	199	197		
Westbound Through	Full 320		225		
Westbound Right	100	180	200		
Northbound Left-Through	Full 254		244		
Northbound Right	25	125	124		
Southbound Left-Through	Full	295	291		
Southbound Right	200	125	125		

Table 7.9 - Brevard Road at Sardis Road / Ridgefield Boulevard						
	Queue Length (ft)					
2022 Scenario	Recommended No Build		Build			
Eastbound Left	125	225	225			
Eastbound Left-Through	Full 1398		1642			
Eastbound Right	50 150		150			
Westbound Left	150	249	250			
Westbound Through	Full 406		262			
Westbound Right	Full 452		453			
Northbound Left	500 587		599			
Northbound Through	Full	792	495			
Northbound Right	225	71	68			
Southbound Left	350	226	233			
Southbound Through	Full	268	236			
Southbound Right	350	288	283			

Table 7.10 - Sand Hill Road at Sardis Road						
	Queue Length (ft)					
2022 Scenario	Recommended Storage	No Build	Build			
Eastbound Left	175	275	274			
Eastbound Through	Full	1222	1188			
Westbound Through	Full 384		1055			
Southbound Left	125	225	225			
Southbound Right	Full	1208	1218			

8.0 Phase 1 Turn Lane Warrants

Turn Lane Warrants were performed for both site access. <u>No turn lanes are recommended for Phase 1.</u> Warrants' graphs can be found in the Appendix.

9.0 2023 Build Phase 2 Conditions

9.1 Trip Generation

Phase 2 is planned to consist of 32 single family dwelling units, 80 low-rise multifamily dwelling units, and 295 mid-rise multifamily dwelling units. Table 9.1 presents the results.

ITE Trip Generation										
Average Weekday Driveway Volumes					24 Hour Volumes	AM Peak Hour		PM Peak Hour		
<u>Phase</u>	Land Use	ITE Land Use Code	<u>Size</u>		<u>Data</u> <u>Source</u>	<u>Volume</u>	Enter	<u>Exit</u>	<u>Enter</u>	<u>Exit</u>
2	Single Family	210	32	Dwelling Units	Equation - Adjacent	364	7	21	21	13
2	Multifamily (Low-Rise)	220	80	Dwelling Units	Equation - Adjacent	564	9	30	30	18
2	Multifamily (Mid-Rise)	221	295	Dwelling Units	Equation - Adjacent	1,606	26	73	76	49
	Phase 2 Trips					2,534	42	124	127	80

9.2 Trip Distribution


Site trips for this proposed development were distributed based existing travel patterns and engineering judgement. The trip distribution model (shown in Figure 6) was confirmed with the NCDOT, and utilizes the following overall directional percentages:


- 20% to/from the west on Brevard Road
- 25% to/from the east on I-40
- 5% to/from the west on I-40
- 5% to/from McIntosh Road
- 20% to/from the west on Sand Hill Road
- 9% to/from the north on Sand Hill Road
- 8% to/from the north on Brevard Road
- 6% to/from the south on Brevard Road
- 2% to/from Ridgefield Boulevard


9.3 2023 Build Volumes


The 2020 build volumes were obtained by summing future no build volumes, Phase 1 trips, and Phase 2 trips. Site trips are shown in Figure 7.

The future build volume totals for AM and PM peaks are shown in Figure 8.









10.0 2023 Capacity Analysis

10.1 Build Level of Service Discussion

The results of the level of service analysis are discussed by intersection below. The LOS results tables can be found in Section 10.2.

Sardis Road at Pond Road

For all scenarios with Sardis Road at Pond Road operating as a stop controlled intersection, the intersection operates as an LOS F for both the AM and PM. Signalizing this intersection would greatly reduce delay for the southbound direction with minimal delay impacts for the east- and westbound direction. This intersection should be signalized in Phase 1. No other improvements are recommended for this intersection.

Pond Road at Site Access 1

This intersection operates as a right-in and out, which will mostly serve Phase 1. The intersection operates at LOS A for the eastbound direction in both AM and PM Peak Hours. No improvements are recommended.

Pond Road at Site Access 2

This intersection is proposed to have full access. The intersection operates at LOS B for eastbound direction and LOS A in the northbound direction in both Peak Hours. Per the turn lane warrents a northbound left turn lane and a southbound right turn lane should be installed with 100' of storage respectively and appropriate taper.

Pond Road at McIntosh Road

The intersection of Pond Road at McIntosh Road is near a school. Being near a school the intersection is expected to operate with high delay during the AM peak hour. For all scenarios, the intersection operates at LOS E in the AM Peak Hour and LOS B in the PM Peak Hour. No improvements are recommended.

Pond Road at Brevard Road

In the No Build Scenario, this intersection operations at LOS C in the AM Peak Hour; however, the intersection degrades to LOS D in the Build Scenario. With split adjustments the Build Scenario with improvements operates at LOS C. <u>Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.</u>

Brevard Road at Farmers Market

In all scenarios, this intersection operations at LOS B or better. <u>Since Brevard Road at Pond Road and Brevard Road at I-40 WB Ramp need timing improvements, then Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.</u>

Brevard Road at I-40 EB Ramp

In all scenarios, this intersection operations at LOS B or better. <u>Since Brevard Road at Pond Road and Brevard Road at I-40 WB Ramp need timing improvements, then Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.</u>

Brevard Road at I-40 WB Ramp / South Bear Creek Road

The intersection of Brevard Road at I-40 WB Ramp and South Bear Creek Road operates at a LOS D in the AM Peak Hour for the No Build Scenario; however, Build Scenario degrades to LOS E. The interaction operates at a LOS C or better in the PM Peak Hour for all scenarios. <u>Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.</u>

Brevard Road at Sardis Road / Ridgefield Boulevard

The intersection of Brevard Road at Sardis Road and Ridgefield Boulevard operates at a LOS D in the AM Peak Hour and LOS E in the PM Peak Hour for all scenarios. <u>No</u> improvements are recommended.

Sand Hill Road at Sardis Road

The intersection of Brevard Road at Sardis Road and Ridgefield Boulevard operates at a LOS D in the AM Peak Hour and LOS E in the PM Peak Hour for all scenarios. <u>No improvements are recommended.</u>

10.2 Level of Service Results

The Level of Service for the 2019 Existing through Build conditions are shown in Tables 10.1 - 10.10.

Table 10.1 - Sardis Road at Pond Road							
Scenario	Overall	Level of Service by Approach (Delay in sec/veh)					
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
	A	AM Peak Hour					
2023 No Build	-	A (9.1)	A (0.0)	-	F (75.3)		
2023 Build Phase 2	-	A (9.2)	A (0.0)	1	F (207.6)		
2023 Build Phase 1 - Signal	B (16.5)	B (15.6)	B (11.0)	-	C (30.2)		
	PM Peak Hour						
2023 No Build	-	B (11.5)	A (0.0)	-	F (>300)		
2023 Build Phase 2	-	B (12.7)	A (0.0)	-	F (>300)		
2023 Build Phase 1 - Signal	B (17.2)	B (14.7)	B (14.2)	-	D (42.5)		

Table 10.2 - Pond Road at Site Access 1							
Scenario	Overall	Level of Service by Approach (Delay in sec/veh)					
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
	AM Peak Hour						
2023 Build Phase 2	-	A (9.9)	-	A (0.0)	A (0.0)		
PM Peak Hour							
2023 Build Phase 2	-	A (9.4)	-	A (0.0)	A (0.0)		

Table 10.3 - Pond Road at Site Access 2							
Scenario	Overall	Level of	Service by App	roach (Delay ir	n sec/veh)		
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
AM Peak Hour							
2023 Build Phase 2	-	B (13.2)	-	A (7.8)	A (0.0)		
2023 Build Phase 2 - Turn Lanes	-	B (13.0)	-	A (7.8)	A (0.0)		
PM Peak Hour							
2023 Build Phase 2	•	B (13.8)	-	A (8.0)	A (0.0)		
2023 Build Phase 2 - Turn Lanes	-	B (13.2)	-	A (8.0)	A (0.0)		

Table 10.4 - Pond Road at McIntosh Road							
Scenario	Overall	Level of	Service by App	roach (Delay ir	n sec/veh)		
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
AM Peak Hour							
2023 No Build	E (67.4)	F (140.8)	-	A (9.1)	B (19.3)		
2023 Build Phase 2	E (65.2)	F (143.8)	-	B (12.1)	C (21.4)		
PM Peak Hour							
2023 No Build	B (11.8)	B (15.3)	-	A (8.0)	B (11.8)		
2023 Build Phase 2	B (12.8)	B (18.9)	-	A (8.2)	B (12.7)		

Table 10.5 - Pond Road at Brevard Road								
Scenario	Overall	Level of	Level of Service by Approach (Delay in sec/veh)					
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound			
	AM Peak Hour							
2023 No Build	C (28.0)	B (15.5)	C (32.6)	D (43.8)	-			
2023 Build Phase 2	D (41.3)	B (15.9)	C (33.2)	F (87.6)	-			
2023 Build Phase 2 - Timing Adjustment	C (26.1)	B (18.9)	C (28.9)	C (34.4)	-			
PM Peak Hour								
2023 No Build	B (17.5)	B (15.5)	B (14.3)	C (29.3)	-			
2023 Build Phase 2	B (19.2)	B (16.2)	B (15.8)	C (32.2)	-			

Table 10.6 - Brevard Road at Farmers Market								
Scenario	Overall	Level of	Service by App	roach (Delay ir	sec/veh)			
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound			
	AM Peak Hour							
2023 No Build	B (13.9)	B (10.5)	B (16.2)	C (31.5)	C (29.4)			
2023 Build Phase 2	B (14.3)	B (10.4)	B (17.2)	C (31.5)	C (29.4)			
2023 Build Phase 2 - Timing Adjustment	B (13.6)	B (11.0)	B (14.9)	C (31.5)	C (29.4)			
PM Peak Hour								
2023 No Build	B (14.2)	B (12.6)	B (11.8)	C (33.7)	C (33.7)			
2023 Build Phase 2	B (14.3)	B (13.0)	B (11.9)	C (33.7)	C (33.7)			


Table 10.7 - Brevard Road at I-40 EB Ramp							
Scenario	Overall	Overall Level of Service by Approach (Delay in sec/veh			n sec/veh)		
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
AM Peak Hour							
2023 No Build	B (10.6)	B (11.1)	A (7.2)	-	C (25.3)		
2023 Build Phase 2	B (11.0)	B (11.6)	A (7.9)	-	C (24.2)		
2023 Build Phase 2 - Timing Adjustment	B (10.8)	B (11.8)	A (7.3)	-	C (24.2)		
PM Peak Hour							
2023 No Build	B (10.5)	A (9.1)	B (11.0)	-	B (18.0)		
2023 Build Phase 2	B (10.8)	A (9.0)	B (11.6)	-	B (19.0)		

Table 10.8 - NC 55 Bypass at I-40 WB Ramp / South Bear Creek Road							
Scenario	Overall	Level of	Level of Service by Approach (Delay in sec/veh)				
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound		
AM Peak Hour							
2023 No Build	D (50.9)	B (18.0)	A (5.7)	E (61.5)	F (125.3)		
2023 Build Phase 2	E (57.1)	B (18.1)	A (6.5)	E (78.4)	F (139.5)		
2023 Build Phase 2 - Timing Adjustment	C (29.6)	D (35.3)	C (24.4)	A (8.1)	D (40.8)		
PM Peak Hour							
2023 No Build	C (21.8)	C (21.5)	C (20.1)	A (5.2)	C (26.2)		
2023 Build Phase 2	C (26.2)	C (22.9)	C (22.5)	A (5.3)	D (35.9)		

Table 10.9 - Brevard Road at Sardis Road / Ridgefield Boulevard						
Scenario	Overall	Level of	Service by App	roach (Delay ir	sec/veh)	
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound	
AM Peak Hour						
2023 No Build	D (45.8)	E (58.4)	E (59.4)	D (39.1)	D (39.2)	
2023 Build Phase 2	D (45.9)	E (57.3)	E (59.7)	D (39.5)	D (39.7)	
PM Peak Hour						
2023 No Build	E (56.7)	E (57.5)	E (76.8)	D (53.0)	D (44.8)	
2023 Build Phase 2	E (58.1)	E (58.9)	E (76.9)	E (56.3)	D (44.7)	

Table 6.11 - Sand Hill Road at Sardis Road						
	Overall	Level of	Level of Service by Approach (Delay in sec/veh)			
Scenario	Overall LOS	Eastbound	Westbound	Northbound	Southbound	
AM Peak Hour						
2023 No Build	D (48.7)	D (38.4)	C (22.8)	-	F (90.5)	
2023 Build Phase 2	D (55.4)	D (42.4)	C (24.4)	-	F (109.5)	
PM Peak Hour						
2023 No Build	E (70.4)	C (25.5)	D (48.2)	-	F (178.5)	
2023 Build Phase 2	E (73.8)	C (24.4)	E (59.1)	-	F (173.5)	

Figure 14 illustrates the recommended improvements for the Phase 2 Build-out conditions.



11.0 2023 Queue Analysis

Queuing analysis was conducted using SimTraffic simulation for the study intersections, based on a standard 15-minute seeding time and a 60-minute recording time. The maximum queue lengths are shown below, along with existing turn lane lengths. All queue reports can be found in the appendix. The queue length lengths are the highest value of AM or PM analysis.

In accordance with NCDOT guidelines, mitigation is required when the Build condition exceeds the No-Build conditions by any of the following minimum thresholds:

- 4. Increase of 50' or more in queue length
- 5. Left-turn and/or right-turn lane warrants (NCDOT's Policy on Street and Driveway Access to North Carolina Highway) are identified
- 6. Build with Capacity Improvements queue exceeds existing storage length

Table 11.1 -Sardis Road at Pond Road								
		(ft)						
2023 Scenario	Recommended Storage	No Build	Build	Signal				
Eastbound Left	150	88	148	208				
Eastbound Through	Full	-	-	284				
Westbound	Full	29	47	303				
Southbound Left	Full	220	664	186				
Southbound Right	150	207	250	182				

Table 11.2 - Pond Road at Site Access 1							
	Queue Length (ft)						
2023 Scenario	Recommended Storage	No Build	Build				
Eastbound	Full	1	41				

Table 11.3 - Pond Road at Site Access 2							
	Queue Length (ft)						
2023 Scenario	Recommended Storage	No Build	Build	Turn Lanes			
Eastbound	Full	-	87	94			
Northbound	Full	-	89	64			

Table 11.4 - Pond Road at McIntosh Road							
	Queue Length (ft)						
2023 Scenario	Recommended Storage	No Build	Build				
Eastbound	Full	720	723				
Northbound	Full	183	621				
Southbound	Full	246	303				

Table 11.5 - Brevard Road at Pond Road							
	Queue Length (ft)						
2023 Scenario	Recommended Storage	No Build	Build	AM Timing			
Eastbound U-Turn	350	59	64	27			
Eastbound Through	Full	159	147	126			
Eastbound Right	350	178	172	204			
Westbound Left	350	221	163	222			
Westbound Through	Full	142	132	124			
Northbound Left	Full	1068	1064	1065			
Northbound Right	100	200	200	200			

Table 11.6 - Brevard Road at Farmers Market						
	Queue Length (ft)					
2023 Scenario	Recommended Storage	No Build	Build			
Eastbound Left	Full	107	95			
Eastbound Through	Full	192	197			
Eastbound Right	Full	51	63			
Westbound Left	325	68	81			
Westbound Through	Full	237	243			
Westbound Right	325	31	33			
Northbound Left	230	99	88			
Northbound Through	Full	83	83			
Southbound Left	Full	70	72			
Southbound Through	150	116	115			

Table 11.7 - Brevard Road at I-40 EB Ramp							
	Queue	Queue Length (ft)					
2023 Scenario	Recommended Storage	No Build	Build				
Eastbound Left	650	180	177				
Eastbound Through	Full	180	506				
Westbound Through	Full	187	191				
Westbound Right	Full	201	185				
Southbound Left	Full	89	98				
Southbound Right	25	124	86				

Table 11.8 - Brevard Road at I-40 WB Ramp / South Bear Creek Road							
	Queue Length (ft)						
2023 Scenario	Recommended Storage	No Build	Build				
Eastbound Left	250	29	29				
Eastbound Through	Full	282	307				
Westbound Left	100	198	196				
Westbound Through	Full	332	313				
Westbound Right	100	185	180				
Northbound Left-Through	Full	163	244				
Northbound Right	25	125	125				
Southbound Left-Through	Full	300	305				
Southbound Right	200	125	125				

Table 11.9 - Brevard Road at Sardis Road / Ridgefield Boulevard							
	Queue	e Length (ft)					
2023 Scenario	Recommended Storage	No Build	Build				
Eastbound Left	125	225	225				
Eastbound Left-Through	Full	1202	1762				
Eastbound Right	50	150	150				
Westbound Left	150	249	249				
Westbound Through	Full	399	432				
Westbound Right	Full	445	456				
Northbound Left	500	594	599				
Northbound Through	Full	1029	1048				
Northbound Right	225	121	70				
Southbound Left	350	276	239				
Southbound Through	Full	262	274				
Southbound Right	350	278	296				

Table 11.10 - Sand Hill Road at Sardis Road							
	Queue Length (ft)						
2023 Scenario	Recommended Storage	No Build	Build				
Eastbound Left	175	275	275				
Eastbound Through	Full	1255	1244				
Westbound Through	Full	1072	1419				
Southbound Left	125	225	225				
Southbound Right	Full	1218	1218				

12.0 Phase 2 Turn Lane Warrants

Turn Lane Warrants were done for both site access. <u>Northbound left lane and southbound right turn lane are warrented for 100' of storage respectively and appropriate taper.</u> Warrants' graphs can be found in the Appendix.

13.0 I-2513 Capacity Analysis

2023 No Build and Phase 2 Build with Improvements scenarios were analyzed with the I-2513 improvements. As Table 13.1 shows both scenarios operate at LOS for AM and PM Peak Hours. Synchro outputs can be found in the Appendix.

Table 13.1 - NC 55 Bypass at I-40 WB Ramp / South Bear Creek Road								
Scenario	Overall	Level of	roach (Delay ir	sec/veh)				
Scenario	LOS	Eastbound	Westbound	Northbound	Southbound			
	A	AM Peak Hour						
2023 No Build	C (27.1)	C (20.3)	C (25.4)	D (37.3)	C (30.5)			
2023 Build Phase 2 with Improvements	C (27.8)	C (21.1)	C (28.3)	D (37.9)	C (29.3)			
	PM Peak Hour							
2023 No Build	C (27.5)	B (16.1)	C (26.2)	C (29.0)	D (37.3)			
2023 Build Phase 2 with Improvements	C (27.2)	B (17.1)	C (26.7)	C (29.0)	D (35.3)			

14.0 Summary and Conclusion

Site Overview

The proposed Pond Road development is located on the northwest of Pond Road at House Lane in Buncombe County, North Carolina. This development is planned to consist of two phases. Phase 1 consists of 280 mid-rise multifamily dwelling units on the south side of the property. Phase 1 is expected to open in 2022. Phase 2 consists of 32 single family dwelling units, 80 low-rise multifamily dwelling units, and 295 mid-rise multifamily dwelling units. Phase 2 is expected to be open in 2023.

The development will utilize two accesses. The southern site access (Site Access 1) will be a right-in/out on Pond Road. The northern site access (Site Access 2) will be a full movement site access on Pond Road.

Trip Generation

ITE Trip Generation										
	Average Weekday Driveway Volumes							Peak our		Peak our
<u>Phase</u>	Land Use	ITE Land Use Code		Size Data Source		<u>Volume</u>	<u>Enter</u>	<u>Exit</u>	<u>Enter</u>	<u>Exit</u>
1	Multifamily (Mid-Rise)	221	280	Dwelling Units	Equation - Adjacent	1,524	24	70	73	46
		Phase 1	Trips			1,524	24	70	73	46
2	Single Family	210	32	Dwelling Units	Equation - Adjacent	364	7	21	21	13
2	Multifamily (Low-Rise)	220	80	Dwelling Units	Equation - Adjacent	564	9	30	30	18
2	Multifamily (Mid-Rise)	221	295	Dwelling Units	Equation - Adjacent	1,606	26	73	76	49
		Phase 2	Trips			2,534	42	124	127	80
	Total Trips						66	194	200	126

Capacity Analysis and Recommendations

Overall, the capacity analysis anticipates adequate traffic capacity at the study intersections. Sardis Road at Pond Road operates at a LOS F as a stop controlled intersection, but is recommended to be signalized. With the addition of site traffic, the study intersections are anticipated to operate at the same levels of service with recommended improvements.

Sardis Road at Pond Road

<u>Signalizing this intersection is recommended in Phase 1.</u>

Pond Road at Site Access 1

No improvements are recommended.

Pond Road at Site Access 2

Northbound left turn and southbound right turn lanes are recommended with 100' of storage respectively and appropriate taper.

Pond Road at McIntosh Road

No improvements are recommended.

Pond Road at Brevard Road

Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.

Brevard Road at Farmers Market

Since Brevard Road at Pond Road and Brevard Road at I-40 WB Ramp need timing improvements, then Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.

Brevard Road at I-40 EB Ramp

Since Brevard Road at Pond Road and Brevard Road at I-40 WB Ramp need timing improvements, then Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.

Brevard Road at I-40 WB Ramp / South Bear Creek Road

Brevard Corridor timings need to be adjusted in the AM after 3 months of Phase 2 being open.

Brevard Road at Sardis Road / Ridgefield Boulevard

No improvements are recommended.

Sand Hill Road at Sardis Road

No improvements are recommended.

Conclusion

In conclusion, this study has reviewed the impacts of the traffic generated by Pond Road development. With the recommended improvements in place, the proposed development and its traffic impacts can be accommodated.